

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-20371 ~~00-00~~

LEASE NAME Dreiling

WELL NUMBER A#2

 Ft. from S Section LI

 Ft. from E Section LI

SEC. 31 TWP. 9 RGE. 24 ~~X~~ or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 4-13-92

Plugging Completed 2:00 PM

TYPE OR PRINT
 NOTICE: Fill out complotely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Thunderbird Drilling Inc.

ADDRESS Box 97, Ellinwood, Kansas 67526

PHONE# (316) 564-2577 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil), Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-13-92 (date)

by Carl Goodrow (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Depth to Top 3928 Bottom 4086 T.D. 4120

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	250	0
				5 1/2	4119	1204

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other were used, state the character of same and depth placed down from feet to feet each.

Filled 5 1/2 Casing w/65/35 w/10% gel, then layed down 1204 ft of 5 1/2 & squeezed a total of 500 lbs Halls, 250 sx cement down 8 5/8. Had max pressure of 300 & shut in pressure of 200.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling Inc

STATE OF Kansas COUNTY OF Barton, ss.


Anna K. Burke (Employee of Operator or Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Anna K. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 14 day of April, 19 92



4-30-93

Notary Public