

KANSAS

Form CP-3  
Rev. 6-26-62

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20075-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 17 1967

8-17-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Imperial Oil Company,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name Sanger Well No. 1

Location CSE-NE Sec. 6 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3900'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 4:00PM Day 13 Month 8 Year 1967

The Above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated with 140 Sx.  
Dakota section from 1800' to 2000'.

Circulated hole with heavy mud. Pulled DP to 2020' and displaced 100 Sx.  
cement thru DP. Pulled DP to 210' and displaced 20 Sx. cement thru DP.  
Pulled DP. set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/17/67

INV. NO. 6159-W

Signed: M. L. Nichols  
Well Plugging Supervisor