

15-065-20516-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 6 1972
CONSERVATION DIVISION
Wichita, Kansas

1-6-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name A. Scott Ritchie,
Complete Address 412 Union Center Building, Wichita, Kansas.
Lease Name Clark Well No. 1
Location W/2-NE-NW Sec. 12 Twp. 9 Rge. (E) (W) 25
County Graham Total Depth 4075'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center Building, Wichita, Kansas. License No.
Operation Completed: Hour 5:30 PM Day 3 Month 1 Year 1972

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-11-72
INV. NO. '4939-W'