

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20408-00-00

JAN 26 1971

CONSERVATION DIVISION  
Wichita, Kansas

1-26-71

Operator's Full Name Albert J. Gebert,

Complete Address 700 Brown Building, Wichita, Kansas.

Lease Name Clark Well No. 2

Location SW-SW-NE Sec. 12 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3850'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Chief Drilling, Incorporated,

Address Suite #905, Century Plaza, Wichita, Kansas. License No.     

Operation Completed: Hour 10:30 PM Day 22 Month 1 Year 1971

The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy-mud. Pulled-DP to 1250' and displaced 100 Sx. cement thru  
DP from 1250' to 925'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Fichale*  
Well Plugging Supervisor

INVOICED

DATE 1/28/71  
INV. NO. 3267-W