

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20318-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1970
CONSERVATION DIVISION
Wichita, Kansas

4-16-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rupe-Gebert-Bell,

Complete Address 222 Brown Building, Wichita, Kansas.

Lease Name Clark Well No. 1

Location CN/2-SE-NW Sec. 12 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4065

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.

Operation Completed: Hour 4:00 AM Day 11 Month 4 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement
thru DP from 1200' to 875'. Pulled DP to 215' and displaced 20 Sx. cement thru DP
from 215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 4/16/70
INV. NO. 1735-W