

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT
15-065-20474-00-60

RECEIVED 7-19-71
STATE CORPORATION COMMISSION
JUL 19 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Schamberger Well No. 1

Location NW-NW-SW Sec. 13 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3976'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:45 PM Day 17 Month 7 Year 1971

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Nichols
Well Plugging Supervisor

DATE 7-20-71
INV. NO. 4031-W