

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-005-20563-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1972
CONSERVATION DIVISION
Wichita, Kansas

8-14-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Waggoner Well No. 1

Location APP C N/2 NW
140' FNL & 1320' FWL Sec. 15 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3853'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor B & B Drilling, Incorporated,

Address 720 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 9:30 AM Day 12 Month 8 Year 1972

The above well was plugged as follows:

242'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement
thru DP from 1300' to 975'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 8-15-72

INV. NO. 6170-42