

KANSAS

*8*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20568-00-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1972

CONSERVATION DIVISION  
Wichita, Kansas

10-24-72

Operator's Full Name Derrick-American Oil, Incorporated,

Complete Address 305 Petroleum Building, Wichita, Kansas.

Lease Name Sauer Well No. 1

Location App:-CE/2-NE-NE Sec. 18 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4125'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.     

Operation Completed: Hour 4:00 AM Day 21 Month 10 Year 1972

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement  
thru DP from 1300' to 975'. Pulled DP to 170' and displaced 30 Cu. Ft. cement thru  
DP from 170' to 95'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 10/27/72  
INV. NO. 6530-4