

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20522-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 31 1972
CONSERVATION DIVISION
Wichita, Kansas

1-31-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Derrick-American Oil, Incorporated,

Complete Address 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name Minium Well No. 1

Location NW-NW-NE Sec. 19 Twp. 9 Rge. (E) (W)25

County Graham Total Depth 4190'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 2:00 AM Day 27 Month 1 Year 1972

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement
thru DP from 1375' to 1050'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. S. Nichols
Well Plugging Supervisor

INVOICED New Address
P. O. Box 17027
Wichita, Ks. 67217

DATE 2-1-72

INV. NO. 5096-W