

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20699-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 9 1974  
9-9-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name C & G Drilling Company,

Complete Address 1107 Union National Building, Wichita, Kansas.

Lease Name Pfeifer Well No. 1

Location NW-SW-SE Sec. 20 Twp. 9 Rge. (E) (W)25

County Graham Total Depth 4120'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Above

Address      License No.     

Operation Completed: Hour 7:00 PM Day 2 Month 9 Year 1974

The above well was plugged as follows:

199'--8 5/8" Surface casing, cement circulated with 140 Sx.  
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement  
thru DP from 1325' to 1000'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 9/10/74  
INV. NO. 9859-W