

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20061-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

1-4-73

Operator's Full Name J. M. Stewart,

Complete Address Suite 500, 200 West Douglas, Wichita, Kansas.

Lease Name Gosselin Well No. 1

Location CSE-SW Sec. 21 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:00 M Day 27 Month 12 Year 1972

The above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 170 Sx.
4115'--5 1/2" Production casing cemented on bottom with 110 Sx. Top perforations from
4051' to 4058'. Annulus between 8 5/8" casing and 5 1/2" casing has been squeezed in
the last year from the surface with 25 sacks gel.

Pushed plug to 4000', sanded well back to 3975' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing (1224') and squeezed well initially with 110 Cu. Ft. cement from
1225' to 900' and followed with 16 sacks gel from 900' to 260' then 30 Cu. Ft. cement
from 260' to 185' and followed with 4 sacks gel from 185 to 25' and finally 10 Cu.

Ft. cement from 25' to bottom of cellar. Maximum pump-in press.-300#. FSIP-150#.
(Mudding and cementing operations by Allied Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. G. Nichols
Well Plugging Supervisor

DATE 1/4/73
INV. NO. 6808-W