

15-068-20565-00-00

Form CP-3
Rev. 6-4-68

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

9-27-72

Operator's Full Name A. Scott Ritchie and Madeira Oil Company,

Complete Address 412 Union Center Building, Wichita, Kansas.

Lease Name Gosselin Well No. 1

Location CNE-SW Sec. 21 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4195'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No.

Operation Completed: Hour 2:00 AM Day 24 Month 9 Year 1972

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu.
Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. G. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9/28/72
INV. NO. 6380-W