

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-03500-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 14 1967  
08-14-1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Joe Espinosa of Southwest Csg. Pulling has this date requested permission to plug the following described well:

Mr. Espinosa guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen,

Complete Address: Logan, Kansas.

Lease Name: Geo. Gano Well No. 2

Location: SE-SE-SE Sec. 36 Twp. 9 Rge. (E)(W) 24

County Graham Total Depth 4040 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Espinosa was instructed to plug the well as follows:

207' -- 8 5/8" Surface pipe, cement circulated.  
4039' -- 5 1/2" Production casing cemented with 150 Sx. Top perf @ 3995'.  
Dakota section from 1030' to 1240'

Sand well back to 3950' and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" casing and squeeze well with 6 Sx. gel followed by 100  
Sx. cement then 16 gel followed with 20 Sx. cement then 3 Sx.  
gel followed with 5 Sx. cement.

Very truly yours,

Conservation Division Agent