



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob White of Empire Drilling Company, has this
date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name: John J. Richmeier Well No. A-1

Location: NE-NE-NE Sec. 2 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4275' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. White was instructed to plug the well as follows:

152'--8 5/8" Surface casing, cement circulated with 115 Sx.
4105'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged
back to 4081'. Top perforations @ 3878' to 3884'.

Sand well back to 3800' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement,
staged.

RECEIVED
STATE CORPORATION COMMISSION

JAN 19 1970

CONSERVATION DIVISION
Wichita, Kansas

1-19-70

Very truly yours,

A. J. Nichols
Conservation Division Agent