

State of Kansas



15-065-20076-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg., 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
CONSERVATION COMMISSION

AUG 28 1967

8 28-67  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this  
date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: 780 4th National Bldg., Wichita, Kansas.

Lease Name: Springer Well No. 1

Location: CSE-NW Sec. 6 Twp. 9 Rge. (E)(W) 25

County Graham Total Depth 4110 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Dakota section from 1800' to 2000'.

Circulate hole with heavy mud. Pull DP to 2030' and displace 100  
Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement  
thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx.  
cement to bottom of cellar.

Very truly yours,

*H. L. Nichols*

Conservation Division Agent