

State of Kansas



15-065-20075-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1967

8-17-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company,

Complete Address: Box #784, Great Bend, Kansas.

Lease Name: Sanger Well No. 1

Location: CSE-NE Sec. 6 Twp. 9 Rge. (E)(W) 25

County Graham Total Depth 3900' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 140 Sx. Dakota section from 1800' to 2000'.

Circulate hole with heavy mud. Pull DP to 2020' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent