



13-065-20318-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

4-16-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Co., has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Rupe-Gebert-Bell,

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Clark Well No. 1

Location: CN/2-SE-NW Sec. 12 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4065 Oil Well

Gas Well      Input Well      SWD-Well      D & A X Lost Hole     

Mr. Fickel was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

  
Conservation Division Agent