



15-065-20563-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1972
CONSERVATION DIVISION
Wichita, Kansas

8-14-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Armbruster of B & B Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Armbruster guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Waggoner Well No. 1

Location: 440' FNL & 1320' FWL of Sec. 15 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 3853' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Armbruster was instructed to plug the well as follows:

242'--8 5/8" Surface casing cement circulated with 150 Sx.
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent