



15-065-20568-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1972

CONSERVATION DIVISION  
Wichita, Kansas

10-24-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Derrick-American Oil Incorporated,

Complete Address: 305 Petroleum Building, Wichita, Kansas.

Lease Name: Sauer Well No. 1

Location: App:-CE/2-NE-NE Sec. 18 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 4125' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

263'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1075'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 110 Cu. Ft. cement thru DP. Pull DP to 170' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. J. Nichols  
Conservation Division Agent