



15-065-20522-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1972

CONSERVATION DIVISION
Wichita, Kansas

1-31-72

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Derrick-American Oil, Incorporated,

Complete Address: 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name: Minium Well No. 1

Location: NW-NW-NE Sec. 19 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4190' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1150'.

Circulate hole with heavy mud. Pull DP to 1375' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

R. L. Nichols
Conservation Division Agent