



15-065-20061-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1973

CONSERVATION DIVISION
Wichita, Kansas

1-4-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: J. M. Stewart,

Complete Address: Suite #500, 200 Wesley Douglas, Wichita, Kansas.

Lease Name: Gosselin Well No. 1

Location: CSE-SW Sec. 21 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4115 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clarke was instructed to plug the well as follows:

255'--8 5/8" Surface casing, cement circulated with 170 Sx.
4115'--5 1/2" Production casing cemented on bottom with 110 Sx. Top perforations from 4051' to 4058'. Annulus between surface casing and production casing has been squeezed with 25 sacks gel.

Push plug to 4000', sand well back to 3975' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 20 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. S. Nichols
Conservation Division Agent