



15-06-20505-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1972

CONSERVATION DIVISION
Wichita, Kansas

9-27-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie & Madeira Oil Company,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Gosselin Well No. 1

Location: CNE-SW Sec. 21 Twp. 9 Rge. (E)(W) 25

County: Graham Total Depth 4195 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

213'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent