

15-065-19112-00-00

Form CP-3
Rev. 6-26-62

kl
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 13 1963
11-13-1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Ida Keith Well No. ± 2

Location NE-SW-SW Sec. 3 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3926

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons Pipe Pulling Co.,

Address: 1450 Maple, Russell, Kansas. License No. 9

Operation Completed: Hour 5:00PM Day 8 Month 11 Year 1963

The Above well was plugged as follows:

150' -- 8 5/8" Surface pipe, cement circulated. 3921' 5 1/2" production casing
cemented with 75 Sx. Top perforations 3903' to 3909'.

Sanded well back to 3890' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 600', circulated heavy gel mud, (19 SX.) Pulled 5 1/2" to 540' and
displaced 20 Sx cement thru casing. Pulled 5 1/2" to 150' and displaced 20
Sx. cement thru casing. Pulled 5 1/2", set birdge @ 30' and 10 Sx cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 11/13/63

INV. NO. 8089-U

Signed: W. D. Fickel
Well Plugging Supervisor