

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1968
CONSERVATION DIVISION
Wichita, Kansas

15-065-20180-00-00

11-12-1968

Operator's Full Name Empire Drilling Company,

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name H. C. Minium Well No. 1

Location NW NW SW
440' FWL & 440' FNL-SW/4 Sec. 7 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4025'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 6:00 AM Day 8 Month 11 Year 1968


The Above well was plugged as follows:

180'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1210' and displaced 100 Sx. cement thru
DP from 1210' to 885'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 11/12/68
INV. NO. 8804-W