

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1972
06-01-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20549-00-00

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Richmeier Well No. 1
Location SE-NE-SW Sec. 18 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 3905'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 11:30 AM Day 30 Month 5 Year 1972

The above well was plugged as follows:

224'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement
thru DP from 1200' to 875'. Pulled DP to 240' and displaced 30 Cu. Ft. cement thru
DP from 240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dickels
Well Plugging Supervisor

INVOICED

DATE 6-1-72

INV. NO. 5789-W