

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

R

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963

12-26-1963

CONSERVATION DIVISION
Wichita, Kansas

15-065-01089-00-00

Operator's Full Name Woodman and Iannitti Drilling Co.,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name Dreilling Well No. 1

Location CSW-NE Sec. 19 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4120

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractors: Above

Address: License No.

Operation Completed: Hour 1:00AM Day 23 Month 12 Year 1963

The Above well was plugged as follows:

212--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx. cement

thru DP. Heavy mud to 180', set plug with 1/4 Sk. hulls and displaced 20 Sx.

cement thru DP. Heavy mud to 40', set plug with 1/2 Sk. hulls and 10 Sx.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. D. Nichols
Well Plugging Supervisor

DATE 12-26-63

INV. NO. 8350-w