

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

20246
15-065 - ~~6-11-67~~ - 00-00

Operator's Full Name Landes Exploration Company & Franks Petroleum Company.

Complete Address P. O. Box #867, Magnolia, Arkansas.

Lease Name Dreiling Well No. 1

Location NE-NW-NE Sec. 19 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3862'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling Company, Incorporated.

Address 339 401 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 16 Month 7 Year 1969

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1270' and displaced 100 Sx. cement thru
DP from 1270' to 945'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245'
to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well plugged as herein stated.

INVOICED

JUL 23 1969
87-23-1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Daniels
Well Plugging Supervisor

DATE 7/23/69

INV. NO. 138-W