

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20689-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1974
12-26-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Wittman "B" Well No. 1

Location NE SW SE Sec. 19 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3930'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 1:30 A Day 24 Month 12 Year 1974

The above well was plugged as follows:

RTD 3930' 8 5/8 csg set at 212' cwc 150 sk. Plg Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1225' thru drill pipe.

Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/3/75
INV. NO. 567-W

Signed: Leo F. Massey
Well Plugging Supervisor