

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas
09-04-1970

15-065-20(365)-00-00

Operator's Full Name Murfin & Kantor,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Nickelson Well No. B-1

Location SW-SE-NE Sec. 20 Twp. 9 Rge. 24W (E) (W)

County Graham Total Depth 3925'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 2:30 PM Day 1 Month 9 Year 1970

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 100 Sx. cement thru
DP from 1240' to 915'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240'
to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 9-4-70

INV. NO. 2485-W