

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1971  
CONSERVATION DIVISION  
Wichita, Kansas

15-065-20479-00-00

08-11-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center Wichita, Kansas

Lease Name Wittman Well No. 1

Location NW NW NW Sec. 20 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3900'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 2:15 A Day 9 Month 8 Year 1971

The above well was plugged as follows:

RTD 3900' 8 5/8 csg set at 209' cwc 150 sk. Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 1125' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 215' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 8-12-71

INV. NO. 4145-4