

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-065-20122-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 29 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
02-29-1968

Operator's Full Name Don E. Pratt,  
Complete Address: Drawer #370, Hays, Kansas.  
Lease Name Nickelson Well No. D-1  
Location CN/2-SE-NE Sec. 22 Twp. 9 Rge. (E) (W) 24  
County Graham Total Depth 4000  
Abandoned Oil Well Gas Well Input Well SWD Well D & A X  
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Leo J. Dreiling & Sons, Incorporated,  
Address: Victoria, Kansas. License No. \_\_\_\_\_  
Operation Completed: Hour 6:15 PM Day 26 Month 2 Year 1968

The Above well was plugged as follows:

201'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud. Pulled DP to 1160' and displaced 100 Sx. cement thru  
DP from 1160' to 840'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with  $\frac{1}{2}$  sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/29/68

INV. NO. 7346-W

Signed: A. L. Dickel

Well Plugging Supervisor