

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20581-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1973
01-08-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company,
Complete Address 217 North Water, Wichita, Kansas.
Lease Name Ronald Nickelson Well No. 1-V
Location CNW-NE Sec. 22 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 4035'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza, Wichita, Ks. License No.
Operation Completed: Hour 9:00 AM Day 5 Month 1 Year 1973

The above well was plugged as follows:

260'--10 3/4" Surface casing, cement circulated with 150 Sx. (9" hole from base of surface to 2100'. 7 7/8" hole from 2100' to TD).
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 150 Cu. Ft. cement thru DP from 1250' to 925'. Pulled DP to 275' and displaced 40 Cu. Ft. cement thru DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 1/9/73
INV. NO. 6826-4