

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20423-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 31 1971
CONSERVATION DIVISION
Wichita, Kansas
03-31-1971

Operator's Full Name Thunderbird Drilling and Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Engleman Well No. 1

Location NW-SW-SE Sec. 24 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3914'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 9:00 AM Day 28 Month 3 Year 1971

The above well was plugged as follows:

258'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from 275'
to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *K. L. Nichols*
Well Plugging Supervisor

DATE 3/31/71
INV. NO. 3476-U