

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1967

12-21-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20108-00-00

Operator's Full Name Kaiser-Francis,

Complete Address 909 Palace Building, Tulsa, Oklahoma.

Lease Name Dinkel Well No. D-1

Location NW-NW-NW Sec. 26 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth ~~3205'~~ 3905'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 7:45 AM Day 19 Month 12 Year 1967

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated.
Dakota section from 925' to 1125'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 100 Sx. cement thru
DP from 1150' to 830'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 12/22/67
INV. NO. 6959.u