

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065 21,458-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name J. B. & E. Oil and Edward P. Leiker

Complete Address Route 17, Box 190, Hays, Kansas 67601

Lease Name Werth "B" Well No. 1

Location SW SE NW Sec. 26 Twp. 9 Rge. 25 (East) (West)

County Graham Total Depth 4150'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations and Allied Cementing Co., Inc.

Address Box 506, Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 1:30 AM Day: 3 Month: September Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows: 8-5/8"-251'-165 sacks common 2% gel. 3% CC  
Anh. 2235-70' Elev. 2560 GL

Hole circulated and filled with mud. 70 sacks cement pumped through  
drill pipe at 2020'. 60 sacks cement pumped through drill pipe at 310'.  
Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and  
hole cemented with 10 sacks cement. Rathole cemented with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP - 09 - 1981  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Conservation Division Agent

INVOICED

DATE 10-29-81

INV. NO. 8137-W