


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-065-00540-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 16 Twp. 10 Rge. 21 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Lewis Well No. 1

Office Address 780 Fourth National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 16, 1958

Application for plugging filed March 16, 1958

Application for plugging approved March 16, 1958

Plugging commenced March 16, 1958

Plugging completed March 16, 1958

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius, Box 731, Hill City

Producing formation Depth to top Bottom Total Depth of Well 3845 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	3-4-58	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with 25 sacks cement at 550 feet. Set No. 2 plug at 220 feet with 15 sacks cement. Set No. 3 plug at 40 feet with 10 sacks cement.


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Stanley J. Bounds (employee of ~~owner~~ or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC. (Signature) By: Stanley J. Bounds V-P 780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of March, 1958

December 19, 1960

Loietta M. Duncan Notary Public.



PLUGGING
FILE SEC 16 T. 10 R. 21.2
BOOK PAGE 89 LINE 44

ED COMMISSION
MAR 27 1958
03-27-1958
CONSERVATION DIVISIC.
Wichita, Kansas

15-065-00540-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

Lewis No. 1
NW NW NE Sec. 16-10S-21W
Graham County, Kansas

Total Depth: 3845'

Commenced: 3-4-58 Completed: 3-17-58

Elevation: 2206' RB
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 217' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Shale	217'		<u>TOPS</u>	
Shale & Shells	710'	Heebner	3451'	(-1245)
Shale, Shells & Sand	1510'	Toronto	3475'	(-1269)
Shale & Shells	1709'	Lansing	3489'	(-1283)
Anhydrite	1760'	Base Kansas City	3719'	(-1513)
Shale & Shells	2070'	Arbuckle	3829'	(-1623)
Shale	2290'	Rotary Total Depth	3845'	(-1639)
Shale & Lime	2920'			
Shale	3010'			
Shale & Shells	3095'			
Shale & Lime	3435'			
Lime	3791'			
Conglomerate	3829'			
Arbuckle	3845'			
Total Depth	3845'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Stanley J. Bamba
Vice-President



Subscribed and sworn to before me this 26th day of March, 1958.

My Commission Expires:

December 19, 1960

STAT.

ED
COMMISSION

Luetta M. Duncan
Notary Public

MAR 27 1958
03-27-1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE	SEC 16 T 70 R 214
BOOK	PAGE 89 LINE 44