

15-065-0037700-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Graham County. Sec. 16 Twp. 10 Rge. (E) 21 (W)

Location as "NE/CNW&SW" or footage from lines NE NE SE

Lease Owner Jones, Shelburne & Farmer, Inc.

Lease Name Lewis Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 8-9 19 53

Application for plugging filed 8-9 19 53

Application for plugging approved 8-9 19 53

Plugging commenced 8-9 19 53

Plugging completed 8-9 19 53

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production Never produced 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Elden Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3864 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	160	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1. Filled hole with heavy mud
2. Pushed plug to 160'
3. Dumped 1/2 sack hulls on top of plug
4. Mixed 15 sacks cement and dumped on top of hulls
5. Filled hole to top
6. Pushed plug to 40'
7. Dumped in 1/2 sack hulls
8. Mixed 10 sacks cement and filled hole to top with same



Name of Plugging Contractor Jones, Shelburne & Farmer, Inc.  
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
John O. Farmer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John O. Farmer  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of August, 19 53  
Bonnie Bernhill  
Notary Public.



PLUGGING  
FILE SEC. 16 T. 10 R. 21 W  
BOOK PAGE 120 LINE 37

15-065-00377-00-00

DRILLER'S LOG

JONES, SHELBURNE & FARMER, INC.

LEWIS #1

NE NE SE Sec. 16-10-21, Graham County, Kansas

Rigged up Rotary Tools 7-29-53  
Tore Down Rotary Tools 8-9-53

Run 4 joints 8 5/8" surface pipe  
set at 160 feet-cemented with 100 sacks  
of cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Shale	0	500
Shale & sand	500	1500
Shale	1500	1727
Anhydrite	1727	1772
Shale & shells	1772	2240
Shale & lime	2240	2870
Lime & shale	2870	2955
Shale & lime	2955	3170
Lime & shale	3170	3330
Shale & lime	3330	3390
Lime & shale	3390	3525
Lime	3525	3705
Lime & shale	3705	3864

TOPS:

Elevation 2229 R. B.  
Heebner 3475  
Toronto 3498  
Lansing 3521  
Base K. C. 3743  
Conglomerate 3817  
Simpson 3824  
Arbuckle 3844  
T. D. 3864

I, John O. Farmer, do hereby certify that the foregoing log is true and  
correst to the best of my knowledge and belief.

John O. Farmer

Subscribed and sworn to before me this 10th day of August, 1953.

Bonnie Berryhill  
Notary Public

My commission expires: April 23, 1956

