

15-065-00348-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Graham County, Sec. 17 Twp. 10 Rge. 21 ~~(E)~~ (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NE  
Lease Owner Victor Drilling Company  
Lease Name Grecian Well No. 1  
Office Address 301 Koch Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 2, 19 52  
Application for plugging filed December 3, 19 52  
Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_  
Plugging commenced December 2, 19 52  
Plugging completed December 2, 19 52  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Unknown  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3870 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	178'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bottom plug at 170' with 15 sacks of cement.  
Set top plug at 40' with 1/2 sacks of hulls and 10 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 4 1952  
12-04-1952  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Corporation  
Address 518 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Gordon L. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling  
518 Petroleum Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of December, 19 52  
Mary L. Hunt  
Notary Public.

My commission expires November 14, 1956

24-2675-S 2-52-20M

PLUGGING  
FILE SEC 17 T 10 R 212  
BOOK PAGE 63 LINE 16

15-065-00348-00-00

CONTRACTOR'S WELL LOG

COMPANY: Victor Drilling Company  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Grecican #1  
 LOCATION: NW NW NE Section 17-10-21  
 Graham County, Kansas

COMMENCED: November 21, 1952  
 COMPLETED: December 2, 1952

0	30	Surface clay and shale
30	85	Shale and shells
85	190	Shale
190	885	Shale, shells and sand
885	1435	Shale and sand
1435	1660	Red Bed and shale
1660	1720	Shale
1720	1755	Anhydrite
1755	1900	Shale and shells
1900	2550	Lime and shale
2550	2635	Lime
2635	2680	Shale
2680	2760	Lime
2760	2860	Lime and shale
2860	2920	Lime
2920	3235	Lime and shale
3235	3870	Lime
	3870	Rotary Total Depth

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 DEC - 4 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 178' of 8 5/8" casing, cemented with 140 sacks of cement.

Dry and abandoned.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Grecican #1 Section 17-10-21 Graham County, Kansas, as reflected by the files of Musgrove Petroleum Corporation

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of December, 1952.

Mary L. Dunn  
Notary Public

My Commission Expires: November 14, 1956.

**PLUGGING**  
 FILE SEC-17-T-10-R-213  
 BOOK PAGE-68 LIB-16