

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

RECEIVED  
 STATE CORPORATION COMMISSION

Form CP-4  
 Rev. 12-15-80

DEC 30 1982  
 12-30-1982  
 CONSERVATION DIVISION  
 Wichita, Kansas

WELL PLUGGING RECORD

15-065-21725-00-00

Give All Information Completely  
 Make Required Affidavit

COUNTY Graham SEC. 20 TWP. 10S RGE. 21 E/W  
 Location as in quarters or footage from lines:  
425' from north line, 940' from east line


Lease Owner Calvin Noah  
 Lease Name Noah Well No. "B" 2  
 Office Address 329 N. Birch, Valley Center, Ks. 67147  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed December 4, 1982  
 Application for plugging filed yes  
 Plugging commenced December 4, 1982  
 Plugging completed December 4, 1982  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3965

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	240	8 5/8	232'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well plugged with 60/40 pozmix, 6% gel, 3%  
 CaCl as follows:  
 1st plug @ 1790' with 20 sacks  
 2nd plug @ 1200' with 80 sacks  
 3rd plug @ 240' with 40 sacks  
 4th plug (solid bridge) 0-40' with 10 sacks  
 10 sacks in rathole  
 10 sacks in mousehole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF KANSAS COUNTY OF SEDGWICK, ss. of Contractor  
John Jay Darrah, Jr., President ~~(employee of owner)~~ or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) By Mallard Drilling Co., Inc.  
405 Century Plaza, Wichita  
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 82

Dianne R. Fowler  
 Dianne R. Fowler Notary Public.

My Commission expires: August 25, 1984

15-065-21725-00-00

D R I L L E R S L O G

COMPANY: CALVIN NOAH  
CONTRACTOR: MALLARD DRILLING CO., INC.  
405 Century Plaza  
Wichita, Kansas 67202

WELL NAME: NOAH "B" 2  
DESCRIPTION:  
425' FNL & 940' FEL  
of SW $\frac{1}{4}$  20-10S-21W

RIG NO.: 1

COUNTY: Graham

TOTAL DEPTH: 3965

ELEVATION:

COMMENCED: November 27, 1982

COMPLETED: December 4, 1982


CASING RECORD:

6 jts. new 8 5/8" 24# surface


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil, sand	0	1525	Ran 232' new 24# 8 5/8" surface casing; set and cemented with 165 sacks common cement, 2% gel, 3% CaC at 240'. Cement circulated. Plug down @ 5:15 p.m., November 27, 1982  Ran 3 drill stem tests  Hole plugged with 60/40 pozmix, 6% gel, 3% CaCl, as follows: 20 sacks @ 1790'; 80 sacks @ 1200'; 40 sacks @ 240'; 10 sacks & solid bridge 0-40'; 10 sacks in mousehold, 10 sacks in rathole. Plugging complete at 8:30 p.m., December 4, 1982.
Sand/shale	1525	1787	
Anhydrite	1787	1835	
Shale	1835	3965	

STATE OF KANSAS )  
                              ) SS.  
COUNTY OF SEDGWICK )

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify that this is a true and correct copy of the log of the Noah "B" 2 well, to the best of my knowledge.

  
John Jay Darrah, Jr., President

SUBSCRIBED AND SWORN to before me this 7th day of December, 19 82.

  
Dianne R. Fowler, Notary Public

My Commission Expires:  
August 25, 1984

RECEIVED  
STATE CORPORATION COMMISSION

DEC 30 1982  
12-30-1982  
CONSERVATION DIVISION  
WICHITA, KANSAS