

15-065-00978-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 10 Twp. 9S Rge. 25W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Waggoner Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 18, 1957

Application for plugging filed November 18, 1957

Application for plugging approved November 18, 1957

Plugging commenced November 18, 1957

Plugging completed November 18, 1957

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4080 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	11-8-57	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 500', Set No. 1 with 25 sacks cement. Set No. 2 plug at 220' with 15 sacks. Filled hole to 30' with mud and set plug with 10 sacks cement.

12-3-57

Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita 2, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Raymond L. Bacon (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: [Signature] V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 1957
December 19, 1960 My commission expires

[Signature] Louetta M. Duncan Notary Public.



PLUGGING
FILE SEC 10 T 9 R 254
BOOK PAGE 63 LINE 29

15-065-00978-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.,
Wichita 2, Kansas

Waggoner No. 1
NW NW SE Sec. 10-9S-25W
Graham County, Kansas

Total Depth: 4080'

Elevation: 2527' RB
Production: D & A

Commenced: 11-8-57 Completed: 11-18-57

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 220' with 150 sacks cement.

Figures indicate bottom of formations:

Sand, Clay & Shale	1050'	<u>TOPS</u>	
Sand & Shale	1200'	Anhydrite	2210' (/ 317)
Shale	2210'	Heebner	3783' (-1256)
Anhydrite	2250'	Toronto	3809' (-1282)
Shale & Shells	2410'	Lansing	3826' (-1299)
Lime & Shale	2565'	Rotary Total Depth	4080' (-1553)
Lime	3040'		
Lime & Shale	3735'		
Lime	4080'		
Total Depth	4080'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Brown
Vice-President



Subscribed and sworn to before me this 29th day of November, 1957.

My Commission Expires:

December 19, 1960

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1957

CONSERVATION DIVISION
Wichita, Kansas

12-3-57

Thelma N. Duncan
Notary Public

PLUGGING
FILE SEC 10 T 9 R25W
BOOK PAGE 63 LINE 29