


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 11 Twp. 9S Rge. 25W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW NW

Lease Owner Tomlinson Oil Company
Lease Name A. Richmeier "e" Well No. 1-C
Office Address 200 W. Doulgas, Suite 1030, Wichita, Ks
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed March 13 19 79
Application for plugging filed (verbally) March 13 19 79
Application for plugging approved (verbally) March 13 19 79
Plugging commenced March 13 19 79
Plugging completed March 13 19 79
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4100'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4100'
Set 1st plug at 1100' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Plug was down at 3:30 a.m., 3-13-79.

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc. 3-19-79

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.



(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 79

Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Tomlinson Oil Company
Abercrombie Drilling, Inc.
A. Richmeier "C" #1 - C KCCZAV
NW NW NW, Section 11-9S-25W
Graham County, Kansas
March 07, 1979
March 13, 1979

0	262	Surface soil, sand and shale
262	1460	Shale
1460	1995	Sand and shale
1995	2218	Shale
2218	2252	Anhydrtie
2252	2700	Shale
2700	2925	Shale and lime
2925	3144	Shale
3144	3490	Shale and lime
3490	4100	Lime and shale
	4100	Rotary Total Depth

Spud hole at 4:00 p.m., March 7, 1979. Drilled 264' of 12 1/4" hole. Ran 7 joints of 8-5/8" - 28# casing. Set at 262' K.B. with 190 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 10:00 p.m., March 7, 1979.

T.D. 4100'. Set 1st plug at 1100' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 3:30 a.m., March 13, 1979.

SAMPLE TOPS:

Anhydrite 2218'
B/Anhydrite 2252'

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION 3-19-79
MAR 19 1979
CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the A. Richmeier "C" #1, NW NW NW, Section 11-9S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
Jack L. Partridge
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 15th day of March, 1979.



Sherrie L. Brooks
Sherrie Brooks, Notary Public

My commission expires 8-21-82.