


15-065-00015-00-00

STATE CORPORATION COMMISSION
All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 13 Twp. 9S Rge. 25 ~~(E)~~ (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Empire Drilling Company
Lease Name J. R. Keith Well No. 2
Office Address 650 Fourth National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 29, 1962 19
Application for plugging filed January 29, 1962 19
Application for plugging approved January 29, 1962 19
Plugging commenced January 29, 1962 19
Plugging completed January 29, 1962 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4075 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Shale	0	1505'	8 5/8"	152'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 550' with 20 sacks cement.
a Plug set at 150' with 20 sacks cement.
Plug set at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1962
CONSERVATION DIVISION
Wichita, Kansas

2-6-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld (Employer/Owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
650 Fourth Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

Subscribed and Sworn to before me this 2nd day of February, 19 62



Lucille H. Harr
Notary Public.

LOG

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: J. R. Keith # 2
 LOCATION: SE SE SE of Section 13-98-25W, Graham County, Kansas
 COMMENCED: January 17, 1962
 COMPLETED: January 29, 1962
 ELEVATION: 2504 KB
 POTENTIAL: D & A

0	to	1505	Surface Shale-Shale
1505	to	1820	Shale-Sand
1820	to	2174	Sand-Red Bed
2174	to	2206	Anhydrite
2206	to	2350	Shale
2350	to	2641	Shale-Shells
2641	to	3800	Line-Shale
3800	to	3835	Line
3835	to	4075	Line-Shale
4075			Rotary Total Depth


SET: 152' of 8 5/8" casing with 100 sacks cement.

SAMPLE TOPS:

Anhydrite	2174	+330
Heebner	3804	-1300
Toronto	3827	-1323
Lansing Kansas C.	3846	-1342
Base Kansas City	4072	-1568
Rotary Total Depth	4075	

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the J. R. Keith # 2, SE SE SE of Section 13-98-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.



Dan J. Kornfeld
Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 2nd day of February, 1962.

Lucille H. Harr
Lucille H. Harr, Notary Public

My commission expires October 21, 1962.