

15-065-00704-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County. Sec. 13 Twp. 9 Rge. 25 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner HARRY GORE  
Lease Name J. R. KEITH Well No. 1  
Office Address 400 BROWN BUILDING, WICHITA, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 2-19-55 19  
Application for plugging filed 2-19-55 19  
Application for plugging approved 2-19-55 19  
Plugging commenced 2-19-55 19  
Plugging completed 2-19-55 19  
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation Depth to top Bottom Total Depth of Well 4072 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	173	8 5/8"	173	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FIRST PLUG AT 160' - 1/2 SACK OF HULLS, 15 SACKS OF CEMENT. TOP PLUG AT 40' - 1/2 SACK HULLS, 10 SACKS OF CEMENT.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 407 BROWN BUILDING, WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, DAN J. KORNFELD (employee of owner) or (owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) DAN J. KORNFELD  
407 BROWN BUILDING, WICHITA, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 23RD day of FEBRUARY, 1955

My commission expires DECEMBER 10, 1956



PLUGGING  
FILE SEC 13 T 9 R 25W  
BOOK PAGE 98 LINE 43

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1955  
CONSERVATION DIVISION  
Wichita, Kansas

Notary Public

2-23-55

L O G

COMPANY: HARRY GORE &  
EMPIRE DRILLING COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: J. R. KEITH #1

LOCATION: NE NE NE, SEC. 13-9-25  
GRAHAM COUNTY, KANSAS

COMMENCED: 2-8-55

COMPLETED: 2-19-55

0	TO	188	SURFACE HOLE
188	TO	875	SHALE AND SAND
875	TO	1205	SHALE, SHELLS AND SAND
1205	TO	1625	SHALE AND SHELLS
1625	TO	2160	SHALE AND SAND
2160	TO	2172	SHALE AND SHELLS
2172	TO	2218	ANHYDRITE
2218	TO	2250	SHALE AND SHELLS
2250	TO	2380	SHALE
2380	TO	2525	SHALE AND SHELLS
2525	TO	3255	LIME AND SHALE
3255	TO	3450	LIME
3450	TO	3590	LIME AND SHALE
3590	TO	3735	LIME
3735	TO	3790	LIME AND SHALE
3790	TO	4072	LIME
4072			R.T.D.

SET 173' OF 8 5/8" SURFACE CASING, CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: <sup>2483</sup>~~2490~~ K.B.

TOPS: ANHYDRITE 2172'; HEEBNER 3795'; LANSING KANSAS CITY 3838'; BASE KANSAS CITY 4066'. R.T.D. 4072'.

D & A

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE J. R. KEITH #1, NE NE NE, SECTION 13, TOWNSHIP 9, RANGE 25 WEST, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 23RD DAY OF FEBRUARY, 1955.

MY COMMISSION EXPIRES DECEMBER 10, 1956

*E. W. Valentine Jr.*  
NOTARY PUBLIC



2-25-55

**PLUGGING**  
FILE SEC 13 T 9 R 25W  
BOOK PAGE 91 LINE 43