


15-065-20563-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County, Sec. 15 Twp. 9S Rge. (E) 25W(W)
Location as "NE/CNW/SE/SW" or footage from lines C N/2 NW
Lease Owner Empire Drilling Co.
Lease Name Waggoner Well No. 1
Office Address 650 Fourth National Building - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 8-12 19 72
Application for plugging filed 8-12 1972
Application for plugging approved 8-12 19 72
Plugging commenced 7:30 8-12 19 72
Plugging completed 9:30 PM 8-12 19 72
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nicholas, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3853 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole		0	242	8 5/8	242	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 1300' w/ 110 Cu ft Plug @ 275' w/30 Cu ft. Plug and Bridge @ 40' w/ 10 cu ft. Hole plugged bu 9:30 PM


RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1972
CONSERVATION DIVISION
Wichita, Kansas

8-16-72

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 720 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
720 Union Center - Wichita, Kansas
(Address)



Subscribed and sworn to before me this 15th day of August, 19 72
Alma A. Neises
Notary Public.

15-065-20563-00-00

(316) 267-0613

B & B DRILLING, INC.
720 Union Center
Wichita, Kansas 67202

August 15, 1972

RECEIVED
STATE CORPORATION COMMISSION

1.05 16 1972

CONSERVATION DIVISION
Wichita, Kansas

8-16-72

DRILLERS LOG

Re: Waggoner #1
C N/2 NW Section 15-9S-25W
Graham County, Kansas

OPERATOR: Empire Drilling, Co.
CONTRACTOR: B & B Drilling, Inc
COMMENCED: August 7, 1972
COMPLETED: August 12, 1972
TOTAL DEPTH: 3853'

Set 8 5/8" @ 242' w/150 sx

0	243	Surface Hole	
243	600	Shale	
600	1675	Shale & Sand	
1675	2255	Shale & Sand	
2255	2295	Anhydrite	
2295	3025	Shale	
3025	3200	Lime-Shale	
3200	3345	Lime & Shale	
3345	3463	Lime & Shale	
3463	3599	Lime	
3599	3815	Lime & Shale	
3815	3853	Lime	
1853		Total Depth	D & A

We certify the above and foregoing to be true and correct copy of the log on the #1 Waggoner, located in Graham County, Kansas.

Bill Lahan President

Alma A. Hesis Notary Public
Subscribed and sworn to before me this 15th day of August, 1972. My commission expires May 31, 1974

