

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-065-21853-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 19 TWP. 9S RGE. 25 SW
 Location as in quarters or footage from lines:

SW NE NE

Lease Owner Houston Hydrolance, International, Inc.
 Lease Name Minium Well No. #1
 Office Address P.O. Box 3723, Victoria, Tx. 77903
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry
 Date Well Completed 9-8-83
 Application for plugging filed 9-8-83
 Plugging commenced 9-8-83
 Plugging completed 9-8-83
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation _____ Depth to top _____ bottom _____ T.D. 4200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	340'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- Spotted 20 sx. cement @ 2340' thru drill pipe.
- Spotted 100 sx. cement @ 1427' thru drill pipe.
- Spotted 40 sx. cement @ 375' thru drill pipe.
- 1/2 sk. hulls, bridge plug, Spotted 110 sx. cement @ 40'.
- Spotted 15 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ernest Sifford (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
401 E. Douglas #500 Wichita
 (Address) Kansas 67202

SUBSCRIBED AND SWORN TO before me this 23rd day of September 1983



David F. Jamis
 David F. Jamis Notary Public.


My Commission expires _____

RECEIVED
 STATE CORPORATION COMMISSION

SEP 26 1983

CONSERVATION DIVISION
 Wichita, Kansas

9-26-83



15-065-21853-00-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Houston Hydrolance International, Inc. P.O. Box 3723, Victoria, Tx. 77903

CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500, Wichita, Ks. 67202

Lease Name Minium Well No. #1

Sec. 19 T. 9S R. 25W Spot SW NE NE

County Graham State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 340' with 200 sx. 2%gel
3% cc

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4200'

Drilling Commenced 9-1-83 Drilling Completed 9-8-83

Formation	From	To	Tops
Cellar	0	7	
Sand, Clay	7	835	
Sand, Shale	835	1650	
Shale	1650	2287	
Shale, Lime	2287	2443	
Shale	2443	2545	
Shale, Lime	2545	3395	
Lime	3395	4200	

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1983

CONSERVATION DIVISION
Wichita, Kansas

9-26-83