


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-065-00620-00-00

NORTH



Locate well correctly on above
Section Plat

Graham

County. Sec. 10 Twp. 9S Rge. 25 (E) 25 (W)

Location as "NE/CNW&SW&" or footage from lines NE NE NW

Lease Owner Tomlinson-Kathol, Inc. & Eugene J. Carter

Lease Name Dinkel Well No. 1

Office Address 414 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1/7/ 19 58

Application for plugging filed 1/7/ 19 58

Application for plugging approved 1/7/ 19 58

Plugging commenced 1/7/ 19 58

Plugging completed 1/7/ 19 58

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elden Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4155 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	234'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud bottom plug @ 700', 20 sacks cement, middle plug @ 180', 20 sacks cement, top plug @ 40' with 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1958
CONSERVATION DIVISION
Wichita, Kansas

1-15-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Tomlinson-Kathol, Inc.
Address 414 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
Warren E. Tomlinson (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson

414 Union Center, Wichita, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 58

Esther Lamore

Notary Public.

Jan. 19, 1961

My commission expires



PLUGGING
FILE SEC. 20 T. 9 R. 25 @
BOOK PAGE 75 LINE 44

15-065-60620-00-00

DRILLERS LOG
TOMLINSON-KATHOL, INC. &
EUGENE J. CARTER
1 DINKEL
NE NE NW, SEC. 20-9S-25W
GRAHAM COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Elevation 2621 KB
Commenced 12/29/57
Completed 1/6/58
D & A

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	136	Sand and Gravel	
136	190	Sand & Clay	8-5/8" Surface casing @ 234'
190	1730	Shale	cemented w/175 sacks
1730	2030	Shells - Shale & red beds	
2030	2312	Shale	
2312	2369	Anhydrite	
2369	2635	Shale	
2635	2671	Lime	
2671	2984	Shale & Lime	
2984	3059	Lime	
3059	3314	Shale & Lime	
3314	3475	Lime	
3475	3790	Shale & Lime	
3790	4000	Lime	Tops: Heebner 3882
4000	4048	Lime & Shale	Toronto 3904
4048	4155	Lime, RTD	Lansing 3919
			Base K.C. 4148
			RTD 4155

Schlumberger

I certify that to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson
Warren E. Tomlinson

State of Kansas
County of Sedgwick

Subscribed and sworn to before me this 10th of January, 1958.

Ethel Lamm
Notary Public

My Commission Expires Jan. 19, 1961

STATE CURATOR'S COMMISSION
JAN 15 1958
CONSERVATION DIVISION
1-15-58

LOGGING
20-9 R25W
BOOK PAGE 75 LINE 49