

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

#45-065-00793-00-01
API NUMBER UNKNOWN

LEASE NAME DREILING

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2 C NW SE

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 21 TWP. 9S RGE. 25 (W)

COUNTY GRAHAM

LEASE OPERATOR ENERGY PRODUCTION, INC.

ADDRESS 6121 E. CENTRAL - WICHITA, KS 67208

PHONE#(316) _____ OPERATORS LICENSE NO. 5016

Date Well Completed 2/1968

Character of Well _____

RECEIVED
STATE CORPORATION COMMISSION
Plugging Commenced 9/14/88
Plugging Completed 9/14/88

(Oil, Gas, D&A SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/14/88

SEP 21 1988 9-21-88 (date)

by CARL GOODROW

(KGO) District Agent's Name)

Is ACO-1 filed? No If not, is well log attached? YES

Producing Formation LANSING - K.C. Depth to Top 4665 Bottom 4068 T.D. 4068

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>8 5/8</u>	<u>233</u>	<u>NONE</u>
				<u>4 1/2</u>	<u>4065</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

ALLIED CEMENTING Co. 9/14/88 - INVOICE 4397 - Pumped 200 SKS 60/40 Pozmix w/ 8% GEL + w/ 2% CCL + 5% S.S. HULLS Pumped in (2) 8" x 8" O.D.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING Co., INC License No. ?

Address PLAINVILLE, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ENERGY PRODUCTION, INC

STATE OF KANSAS COUNTY OF SEDOGWICK, ss.

Ed Leith (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) E. Leith

(Address) 1509 ROBIN RIDGE CR WICHITA, KS

SUBSCRIBED AND SWORN to before me this 19 day of Sept, 19 88

MARY KAY JOLLEY
NOTARY PUBLIC
STATE OF KANSAS

Mary Kay Jolley
Notary Public

My Appt. Exp. _____

My Commission Expires: 7-30-90

15-065-00793-00-01

CONTRACTOR'S WELL LOG

OWNER:
CONTRACTOR:
FARM:
LOCATION:
TEST:

James M. Stewart
Abercrombie Drilling, Inc.
#2 DRILLING
NW SE, Section 21-98-25W
Graham County, Kansas
Base of the Kansas City (4068')

0	700	Old Hole - No Cuttings
700	1107	Shale
1107	1630	Shale & Sand
1630	1850	Shale
1850	2040	Sand
2040	2260	Shale
2260	2295	Anhydrite
2295	2525	Shale
2525	2970	Shale & Lime
2970	3565	Lime & Shale
3565	3630	Lime
3630	3856	Lime & Shale
3856	4068	Lime
	4068	Rotary Total Depth

This was intended to be a washdown job which was commenced 1-24-68. Drilled out of old hole at 540' and could not get back into it.

Ran 4-1/2" casing and set plug @4045'. Plug was down 3:30 a.m., 2-2-68.

ELEVATION:

2611 K. B.
2610 D. F.
2604 G. L.

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1968

CONSERVATION DIVISION
Wichita, Kansas


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Abercrombie Drilling, Inc., does hereby certify that the above and foregoing is a true and correct copy of the log of the #2 DRILLING, NW SE, Sec. 21-98-25W, Graham County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

Jack K. Wharton
Jack K. Wharton

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, as of the 6th day of February, 1968.

Mildred Saxton
Mildred Saxton
Notary Public



My Commission Expires:

October 5, 1968