

15-065-00621-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 21 Twp. 9S Rge. (E) 25 (W)

Location as "NE/CNW/SE/SW" or footage from lines. SE SE SE

Lease Owner Tomlinson-Kathol, Inc. & Eugene J. Carter

Lease Name Dreiling Well No. 1

Office Address 414 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/28/ 19 57

Application for plugging filed 12/28/ 19 57

Application for plugging approved 12/28/ 19 57


Plugging commenced 12/28/ 19 57

Plugging completed 12/28/ 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Elden Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4120 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	217	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud, bottom plug @ 700', 20 sacks cement middle plug @ 180', 20 Sacks cement, top plug @ 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 4 1958  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Tomlinson-Kathol, Inc. 1-4-58  
Address 414 Union Center Bldg. - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Warren E. Tomlinson

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Warren E. Tomlinson

414 Union Center - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 1958

Esther Lamore  
Notary Public.

My commission expires Jan. 19, 1961

PLUGGING  
FILE SEC 21 T 9 R 256  
BOOK PAGE 73 LINE 31



15-005-00621-00-00

DRILLERS LOG  
TOMLINSON-KATHOL, INC. &  
EUGENE J. CARTER  
# 1 DREILING  
SE SE SE, SEC. 21-9S-25W  
GRAHAM COUNTY, KANSAS

Contractor - Tomlinson-Kathol, Inc.

Elevation 2611 KB  
Commenced 12/17/57  
Completed 12/28/57  
D & A

<u>From</u>	<u>Tom</u>	<u>Description</u>	<u>Remarks</u>
0	84	Sand & Gravel	
84	200	Sand & Shale	8-5/8 @ 217' w/165 Sbs cemen
200	217	Sand & Shale	
219	980	Shale & Shells	
980	2235	Shale	
2235	2276	Anhydrite	
2276	2475	Shale	
2475	2800	Shale & Lime	
2800	2891	Shale	
2891	3300	Shale & Lime	
3300	3410	Lime	
3410	3695	Lime & Shale	
3695	3804	Shale & Lime	
3804	3867	Lime & Shale	
3867	3950	Lime	
3950	3958	Lime & Shale	
3958	4051	Lime	
4051	4060	Lime & Shale	
4060	4120	Lime	

I certify that to the best of my knowledge and belief, the above represents a true and accurate Driller's Log record of the captioned well.

Warren E. Tomlinson  
Warren E. Tomlinson

State of Kansas  
County of Sedgwick

Subscribed and sworn to before me this 2nd day of January, 1958.

Esther Laman  
Notary Public

My Commission Expires Jan. 19, 19561.

1-3-58

PLUGGING  
SEC 2, T. 9, R. 25W  
BOOK PAGE 73 LINE 31