

15-065-20061-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely.
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Graham County, Sec. 21 Twp. 9 Rge. 25 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner J. M. Stewart

Lease Name Gosselin Well No. #1

Office Address 200 W. Douglas Suite 500 Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 12-22-72 _____ 19__

Plugging completed 12-27-72 _____ 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4115' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4115'	1232.54'
				8 5/8"	255'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 4025'. Mixed and ran 5 sacks cement thru dump bailer.

Squeeze hole with 20 sacks gel and 150 sacks 50/50 poxmix and 6% gel.

RECEIVED
STATE CORPORATION COMMISSION

DEC 29 1972

CONSERVATION DIVISION
Wichita, Kansas

12-29-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.

Address Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. C. Spencer Sec.

(Address) _____

Subscribed and Sworn to before me this 28 day of December, 1972

Sidney D. Miller
Notary Public.

My commission expires 24 October 1976



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

15-065-20061-00-00

GOSELIN #1
 C SE SW SECTION 21-9S-25W
 GRAHAM COUNTY, KANSAS

COMMENCED: JULY 10, 1967
 COMPLETED: JULY 19, 1967

OPERATOR - JAMES M. STEWART

DEPTH		FORMATION	REMARKS
FROM	TO		
0	60	SURFACE SOIL	
60	80	SAND	
80	155	SHALE, SAND AND PYRITE	
155	170	SAND	
170	255	BLUE SHALE	RAN 13 JOINTS 8-5/8" CASING, SET 2 255' w/170 BAGS CEMENT.
255	1100	SHALE AND SHELLS	
1100	1230	SAND	
1230	1350	SHALE	
1350	1800	SHALE AND SAND	
1800	1895	SHALE AND SHELLS	
1895	1990	SAND	
1990	2230	SHALE AND RED BED	
2230	2273	ANHYDRITE	
2273	2450	SHALE	
2450	2635	SHALE AND SHELLS	
2635	3330	LIME AND SHALE	
3330	3425	LIME	
3425	3480	LIME AND SHALE	
3480	3585	LIME	
3585	3878	LIME AND SHALE	
3878	3923	LIME	
3923	3970	LIME AND SHALE	
3970	4115	LIME	
4115	TD		RAN 131 JOINTS 5 1/2" CASING, SET # 4115' w/100 BAGS CEMENT.

12-20-72
 RECEIVED
 STATE CORPORATION COMMISSION
 DEC 20 1972
 CONSERVATION DIVISION
 Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C SE SW SECTION 21-9S-25W, GRAHAM COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 25TH DAY OF JULY, 1967, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.

