

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 179-21082 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Lester Senesac/LESTER SENESAC OIL & GAS EXPL. KCC LICENSE # 31701
(owner/company name) (operator's)

ADDRESS P.O. Box 305 CITY Hill City

STATE Kansas ZIP CODE 67642 CONTACT PHONE # (913) 674-2298

LEASE Reidel WELL# 1 SEC. 15 T. 9s R. 26 (~~East~~/West)

170'S NE-NE - NE SPOT LOCATION/QQQQ COUNTY Sheridan

500 FEET (in exact footage) FROM S/(N) (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 250.28 CEMENTED WITH 160 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2620/2628 T.D. 4118 PBTD _____ ANHYDRITE DEPTH (2310-2348)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1st Plug @ 2340' w/25sks)(2nd Plug @ 1350'w/100sks)
(3rd Plug @ 300'w/40sks)(4th Plug @ 40'w/10sks)(10sks In Mouse Hole)(15sks In Rat Hole)
200sks Total 60/40Poz 6%Gel w/1#FS/sk By Allied Cementing (Completed @ 4:15PM 1/7/96)
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No Log IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Lester Senesac PHONE# (913) 674-2298

ADDRESS P.O. Box 305 City/State Hill City, Kansas 67642

PLUGGING CONTRACTOR Discovery Drilling, Inc KCC LICENSE # 31548
(company name) (contractor's)

ADDRESS P.O. Box 763 Hays, Kansas 67601-0763 PHONE # (913) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4:15 PM 1/7/96

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-15-96 AUTHORIZED (OPERATOR) AGENT: Lester V. Senesac
(signature)